Dated 25th March 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 15th April 1918 for restoring the Anehalli Mulagankere tank, R. No. 160 of the Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Anehalli Mulagankere tank, R. No. 160 of Mulbagal Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for restoring the Anehalli Mulagankere tank, Registered No. 160 of Mulbagal Taluk.

Items of work	Per	Quantity
Bund R. L. 54·50		
Earthwork to bund	C. yd.	3,058
Removing silt	"	304
Turfing to slopes	S. yd.	4,956
Fixing grade stones with index	No.	25
Fixing date stone	"	1
Fixing registered number stone	"	1
Gauge stone	"	2
B. M. stones	C. yd.	549
Old stone work for revetment	"	1,098
New stone work	"	255
Gravel backing		
Waste weir 133 ft. long.		
Burnt brick in surki mortar	C. ft.	1,127
Burnt stone slabs	S. ft.	554
New stone work	C. yd.	130
Chunam plastering	Sqr.	4·00
Sluice.		
Earthwork cutting and filling	C. yd.	80
Earthwork excavation	"	195
Burnt brick in surki mortar	C. ft.	456
Burnt stone slabs	S. ft.	207
Plastering with surki mortar	Sqr.	3·50

V. V. KARVE,
Offg. Executive Engineer.

TUMKUR DIVISION.

Notification.

Attention of the public is invited to notification published in page 243 of *Mysore Gazette*, Part IV, dated 21st March 1918, calling for the tenders for constructing A.-V. School at Pavagada. The last date of the tender is 20th March 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 10th of April 1918, for restoring Adlapur tank, Registered No. 21,

Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 191 .

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M. except on Sundays and Holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Adlapur tank, Registered No. 21, of Tumkur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of restoring Adlapur tank, Registered No. 21, of Tumkur Taluk.

No.	Items of work	Per	Quantity
	Bund R. L. 57·00—		
1	Earthwork to bund including watering, etc.	C. yd.	3,930
2	Earthwork excavating foundation for revetment	"	2,084
3	New stone work	"	2,268
4	Gravel backing	"	1,207
5	Turfing	S. yd.	56·37
6	Removing and fixing grade stones with bed slabs including cutting figures and painting.	Each	23
7	Index stones	"	23
8	Date stone	"	1
9	Register No. stones...	"	1
10	Bench mark stones	"	2
11	Gauge stones	"	1
12	Cutting grips in old bund to receive new earth and clearing jungle ...	Grade	22
	Sluices—		
13	Examining and reparing left sluice No. 1	Lump	sum Rs.
	Constructing right sluice sill at R. L. 44·00 at C. S. No. 10—		
14	Cut ing the bund and refilling earthwork	C. yd.	225
15	Burnt brick in surki mortar	C. ft.	1,117
16	Burnt stone slabs dressed	S. ft.	276
17	Surki plastering	Sqr.	9·44
18	Gibbet stones	S. ft.	2·7
19	Cutting upper and lower orifices and holes in slabs on top of gibbets ...	Lump	sum Rs.
20	Plug and rod, etc., complete	Lump	sum Rs....
	Waste weir—		
21	Earthwork excavating foundation for the wall, toe wall, etc., apron and forming wing bunds with necessary earthwork, etc.	Lump	sum Rs.
22	Burnt brick in surki mortar	C. ft.	954
23	Burnt stone slabs dressed	S. ft.	279
24	Surki plastering	Sqr.	2·60
25	Rough stone apron	C. yd.	267
	Right waste weir 200′ long at R. L. 52·00—		
26	Excavating foundation for body wall and apron and forming wing bund by clearing draft of the weir.	Lump	sum Rs.
27	Burnt brick in surki mortar	C. ft.	1,638
28	Plastering with cement ½″ thick to old body wall	Sqr.	2·25
29	Surki plastering	"	4·10
30	Burnt stone slabs	S. ft.	579
31	Rough stone work new	C. yd.	426
32	Old stone work removing and resetting	"	178
33	Jelly filling for the space of old stone removed	"	45
	Distribution—		
34	Constructing two acqueducts for the right and left sluice channel ...	Lump	sum Rs.

Abstract Notification.

Attention of the public is invited to notifications published in *Mysore Gazette*, dated 20th March 1918, pages 248 and 249, Part IV, calling for tenders for extending and improving A.-V. School at Tumkur and constructing A.-V. School at Pavagada. The last dates therein for tenders are extended up to 6th April 1918. The other conditions remain the same.

N. G. KRISHNA IYENGAR,
Offg. Executive Engineer.